

GSP CONSULTING

September 18, 2015

Pender County
Planning and Community Development
805 S. Walker Street
Burgaw, NC 28425

Re: Wyndwater – Phase 2B
Project Narrative

Dear Mr. Meredith:

This phase of the Wyndwater project is a revision to the previously approved Phase 2. This phase of the project will increase the total unit count of Phase 2 from 56 lots to 63 lots. This phase of the project will also include a Public waterline extension and a sewer main extension that will be owned and maintained by Pluris, LLC. The primary stormwater measures for this site will be a closed conduit system that will direct the runoff to a proposed wet detention basin that will be designed to control the peak runoff from the 10-year storm event and will be analyzed for the 100-year storm event to prevent flooding of the proposed development. This project will require approvals from DENR-Public Water Supply Section for the water line extension, NCDOT for the subdivision street, NCDENR-Division of Water Resources for the sewer extension & NCDENR-Division of Energy, Mineral and Land Resources for Stormwater & Erosion & Sediment Control. The traffic for this phase of the development are estimated to be approximately 603 total daily trips with 47 in the AM peak hour and 64 in the PM peak hour based on the ITE Trip Generation Manual 8th edition using ITE Code 210 for single family homes.

Please contact me immediately at (910) 442-7870 or gpape@gsp-consulting.com if you have any questions or require additional information.

Sincerely,

GSP CONSULTING, PLLC.



Garry S. Pape, P.E.